


BRUHAT BANGALORE MAHANAGARA PALIKE



**Asst.Executive Engineer,
Shettyhalli Sub Division,**

Name of Work Improvements of CC Roads in 3rd, 4th, 5th, 6th & 7th Cross Near Bylappa Circle At Prashanth Nagar in Ward No.13, Shettyhalli Sub Division.

Est Cost:50.00 Lakhs

Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Name of Work: Improvements of CC Roads in 3rd, 4th, 5th, 6th & 7th Cross Near Bylappa Circle At Prashanth Nagar in Ward No.13, Shettyhalli Sub Division. .

					Est .Cost Rs.50.00 Lakhs				
SI No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300-3. Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 142/ Item No. 19.1/ PWD SR 2016-17								
	4th Cross	cum	1	130.00	0.90	0.50	58.50		
	3rd Cross(Muthuraya Swamy Temple)		1	75.00	0.90	0.50	33.75		
	4thCross(Katumraya Swamy Temple)		1	72.00	0.90	0.50	32.40		
	5thCross(Katumraya Swamy Temple)		1	60.00	4.00	0.50	120.00		
	8th Cross		1	90.00	0.90	0.50	40.50		
	9th Cross		1	60.00	0.90	0.50	27.00		
	9th A Cross		1	55.00	0.90	0.50	24.75		
	9th B Cross		1	55.00	0.90	0.50	24.75		
	10th Cross		1	70.00	0.90	0.50	31.50		
	1st A Cross		1	33.00	0.90	0.50	14.85		
	1st B Cross		1	33.00	0.90	0.50	14.85		
	1st Main Road		1	35.00	0.90	0.50	15.75		
	6th Cross Dasarahalli Main Road		1	60.00	0.90	0.50	27.00		
	4th Cross		2	130.00	0.45	0.40	46.80		
	3rd Cross(Muthuraya Swamy Temple)		2	75.00	0.45	0.40	27.00		
	4thCross(Katumraya Swamy Temple)		2	72.00	0.45	0.40	25.92		
	5thCross(Katumraya Swamy Temple)		2	60.00	0.45	0.40	21.60		
	8th Cross		2	90.00	0.45	0.40	32.40		
	9th Cross		2	60.00	0.45	0.40	21.60		
	9th A Cross		2	55.00	0.45	0.40	19.80		
	9th B Cross		2	55.00	0.45	0.40	19.80		
	10th Cross		2	70.00	0.45	0.40	25.20		
	1st A Cross		2	33.00	0.45	0.40	11.88		
	1st B Cross		2	33.00	0.45	0.40	11.88		
	1st Main Road		2	35.00	0.45	0.40	12.60		
	6th Cross Dasarahalli Main Road		2	60.00	0.45	0.40	21.60		
	4th Cross		2	130.00	0.45	0.30	35.10		
	3rd Cross(Muthuraya Swamy Temple)		2	75.00	0.45	0.30	20.25		
	4thCross(Katumraya Swamy Temple)		2	72.00	0.45	0.30	19.44		
	5thCross(Katumraya Swamy Temple)		2	60.00	0.45	0.30	16.20		
	8th Cross		2	90.00	0.45	0.30	24.30		
	9th Cross		2	60.00	0.45	0.30	16.20		
	9th A Cross		2	55.00	0.45	0.30	14.85		
	9th B Cross		2	55.00	0.45	0.30	14.85		
	10th Cross		2	70.00	0.45	0.30	18.90		
	1st A Cross		2	33.00	0.45	0.30	8.91		

[Handwritten signature]

ತಾಂತ್ರಿಕ ಸಹಾಯಕರು

	1st B Cross		2	33.00	0.45	0.30	8.91		
	1st Main Road		2	35.00	0.45	0.30	9.45		
	6th Cross Dasarahalli Main Road		2	60.00	0.45	0.30	16.20		
				3.00			987.24	172.57	170368.01
2	KSSRB M400-7 Construction Of granular sub -base by providing coarse graded crushed stone aggregates of granite / trap / basalt material spreading in uniform layers with motor grader on prepared surface,mixing by mix in place method with rotavator at OMC,and compacting with vibratory roller to achive the desired density. complete asper specification. By mix in place method for Grading II Material KSSRB Page No 156 Item No 20.6 and 20.6.3								
	4th Cross	Cum	1	130.00	0.90	0.20	23.40		
	3rd Cross(Muthuraya Swamy Temple)		1	75.00	0.90	0.20	13.50		
	4thCross(Katumraya Swamy Temple)		1	72.00	0.90	0.20	12.96		
	5thCross(Katumraya Swamy Temple)		1	60.00	4.00	0.20	48.00		
	8th Cross		1	90.00	0.90	0.20	16.20		
	9th Cross		1	60.00	0.90	0.20	10.80		
	9th A Cross		1	55.00	0.90	0.20	9.90		
	9th B Cross		1	55.00	0.90	0.20	9.90		
	10th Cross		1	70.00	0.90	0.20	12.60		
	1st A Cross		1	33.00	0.90	0.20	5.94		
	1st B Cross		1	33.00	0.90	0.20	5.94		
	1st Main Road		1	35.00	0.90	0.20	6.30		
	6th Cross Dasarahalli Main Road		1	60.00	0.90	0.20	10.80		
	4th Cross		2	130.00	0.45	0.15	17.55		
	3rd Cross(Muthuraya Swamy Temple)		2	75.00	0.45	0.15	10.13		
	4thCross(Katumraya Swamy Temple)		2	72.00	0.45	0.15	9.72		
	5thCross(Katumraya Swamy Temple)		2	60.00	0.45	0.15	8.10		
	8th Cross		2	90.00	0.45	0.15	12.15		
	9th Cross		2	60.00	0.45	0.15	8.10		
	9th A Cross		2	55.00	0.45	0.15	7.43		
	9th B Cross		2	55.00	0.45	0.15	7.43		
	10th Cross		2	70.00	0.45	0.15	9.45		
	1st A Cross		2	33.00	0.45	0.15	4.46		
	1st B Cross		2	33.00	0.45	0.15	4.46		
	1st Main Road		2	35.00	0.45	0.15	4.73		
	6th Cross Dasarahalli Main Road		2	60.00	0.45	0.15	8.10		
							298.02	1582.58	471640.49
3	KSSRB M600-1 Construction Of dry lean cement concrete mix CC1:5:10 With OPC cement @160kgs,with 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum sub-base over a prepared sub-grade with (course and fine aggregate conforming to IS:383) aggregate cement ratio not to exceed 15:1. Aggregate gardation after blending to br as per Table 600-1, cement content not to be less than 160kg/cum, optimum moisture content to be less than 10Mpa at 7days, mixxed in a batching plant, transported to site, laid with a paver with electronic sensor, comacting with 8-10 tonnes vibratory roller,finishing and curing complete asper Specification KSSRB:Page No 176, Item No 22.2 and 22.2.1								
	4th Cross	Cum	1	130.00	0.90	0.15	17.55		
	3rd Cross(Muthuraya Swamy Temple)		1	75.00	0.90	0.15	10.13		
	4thCross(Katumraya Swamy Temple)		1	72.00	0.90	0.15	9.72		
	5thCross(Katumraya Swamy Temple)		1	60.00	4.00	0.15	36.00		

[Handwritten signature]

[Handwritten signature]
ಪಾಂಡೆ ಸಹಾಯಕರು

8th Cross		1	90.00	0.90	0.15	12.15		
9th Cross		1	60.00	0.90	0.15	8.10		
9th A Cross		1	55.00	0.90	0.15	7.43		
9th B Cross		1	55.00	0.90	0.15	7.43		
10th Cross		1	70.00	0.90	0.15	9.45		
1st A Cross		1	33.00	0.90	0.15	4.46		
1st B Cross		1	33.00	0.90	0.15	4.46		
1st Main Road		1	35.00	0.90	0.15	4.73		
6th Cross Dasarahalli Main Road		1	60.00	0.90	0.15	8.10		
4th Cross		2	130.00	0.45	0.10	11.70		
3rd Cross(Muthuraya Swamy Temple)		2	75.00	0.45	0.10	6.75		
4thCross(Katumraya Swamy Temple)		2	72.00	0.45	0.10	6.48		
5thCross(Katumraya Swamy Temple)		2	60.00	0.45	0.10	5.40		
8th Cross		2	90.00	0.45	0.10	8.10		
9th Cross		2	60.00	0.45	0.10	5.40		
9th A Cross		2	55.00	0.45	0.10	4.95		
9th B Cross		2	55.00	0.45	0.10	4.95		
10th Cross		2	70.00	0.45	0.10	6.30		
1st A Cross		2	33.00	0.45	0.10	2.97		
1st B Cross		2	33.00	0.45	0.10	2.97		
1st Main Road		2	35.00	0.45	0.10	3.15		
6th Cross Dasarahalli Main Road		2	60.00	0.45	0.10	5.40		
						214.20	3986.66	853942.57

4 Cement concrete pavement. Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregates, with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) & spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane, sealant primer, joint sealant, admixtures as approved, including curing, finishing to lines and grades as per drawing complete as per specifications. **M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum) Page o 177 Item No 22.6.1**

4th Cross	Cum	1	130.00	4.20	0.15	81.90		
3rd Cross(Muthuraya Swamy Temple)		1	75.00	4.20	0.15	47.25		
4thCross(Katumraya Swamy Temple)		1	72.00	4.00	0.15	43.20		
5thCross(Katumraya Swamy Temple)		1	60.00	4.00	0.15	36.00		
8th Cross		1	90.00	2.00	0.15	27.00		
9th Cross		1	60.00	4.00	0.15	36.00		
9th A Cross		1	55.00	4.00	0.15	33.00		
9th B Cross		1	55.00	4.00	0.15	33.00		
10th Cross		1	70.00	4.00	0.15	42.00		
1st A Cross		1	33.00	4.00	0.15	19.80		
1st B Cross		1	33.00	4.00	0.15	19.80		
1st Main Road		1	35.00	4.00	0.15	21.00		
6th Cross Dasarahalli Main Road		1	60.00	4.00	0.15	36.00		
						475.95	6217.96	2959438.06





ತಾಂತ್ರಿಕ ಸಹಾಯಕರು
ಮಾಲಿ ಅಭಿವೃದ್ಧಿ ಮತ್ತು ಸಂರಕ್ಷಣೆ

[illegible]


Name of Work

Improvements of CC Roads in 3rd, 4th, 5th, 6th & 7th cross Near Bylappa Circle at Prashanth Nagar in Ward No. 13, Shettyhalli Sub-division



Typical c/s of cc Road surface

Index - 



Asst. Engineer
Ward No. 13


Asst. Executive Engineer
Shettyhalli Sub Division, Dasarahalli Zone
BBMP Bangalore.